

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1967

8-4-67

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 28, 1967.

Operator's Full Name Aylward Drilling Company

Complete Address 909 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Donovan "C" Well No. # 1

Location NW SW SE Sec. 6 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4821'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation, Inc.

Address Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 11:30 A.M. Day 2nd Month August Year 1967

The above well was plugged as follows:

200' of 8 5/8" surface pipe, cement circulated. 4821' of 5 1/2" long string,
cemented with 75 sacks. Top perforation 4762'. Bottom of the hole was sanded
to 4750', and cemented with 5 sacks, through the dump bailer, cement from
4750' to 4710'. 2876' of 5 1/2" long string was recovered from the hole. Fluid
in the hole was bailed down to 200', bridge plug and rock bridge from 200' to
190', and cemented with 25 sacks, with cement from 190' to 115'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10
sacks, from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/4/67
INV. NO. 6099-u