

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1965  
1-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 North Broadway, Wichita, Kansas

Lease Name Vestal Cook Well No. # 1

Location SE/4 Sec. 7 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4845

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 11:00AM Day 10th Month Jan. Year 1965

The Above well was plugged as follows:

368' of 8 5/8" surface pipe, cemented with 200 sacks. 4844' of 5 1/2" long  
string, cemented with 200 sacks. Plug back to 4820'. Top perforation  
4722'. Bottom of the hole was sanded to 4700', and cemented with 5 sacks.  
Fluid in the hole was at 280'. Bridge plug was set on fluid at 280', and  
10' of rock bridge, and cemented with 25 sacks. Hole was filled with mud  
to 40', and 10' of rock bridge, and cemented with 10 sacks to the base  
of the cellar.

3608' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1-12-65

INV. NO. 499-W