

15-007-10352-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 1975  
12-4-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mobil Oil Corp

Complete Address Box 1934 Oklahoma City, OK

Lease Name V.L. Cook Well No. 1

Location NE/SW/SW Sec. 7 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4890

Abandoned Oil Well  Gas Well  <sup>AW</sup> Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 10:00 AM Day 28 Month 11 Year 1975

The above well was plugged as follows:

340 ft 8 5/8 surface cemented with 275 sacks. 4889 ft 5 1/2 long string  
cemented with 200 sacks. Top perf. 4850 ft. Sand to 4800 ft, 5 sacks  
cement with bailer. Pulled 3100 ft 5 1/2. Set 10 ft rock bridge at  
250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed *[Signature]*  
Well Plugging Supervisor

INVOICED

DATE 12-12-75

INV NO. 2401-w