



CP3

GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date 20 September, 19 58, authorized the following plugging operation:

Operator's Full Name: Continental Oil Co.

Complete Address: Box 161, Great Bend, Kans.

Lease Name: Helen Porterfield Well No. 2

Location: 2190 fr.W. 1650 fr.S Sec. 32 Twp. 34 Rge. 10 (E) (W) X

County: Barber Total Depth: 5267

Oil Well ~~X~~ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

267' of 8 5/8" surface casing circulated with 200 sack cement.  
Fill hole with heavy drilling mud to 250'. Set cementing plug at  
250' with on top 1/4 sack hulls. Place 20 sack cement through drill  
pipe. Heavy drilling mud to 40' with 1/4 sack hulls, cementing  
plug and cement to base of cellar. Tie cap plug to top of pipe.

Very truly yours,

Signed: [Signature]  
 Conservation Division Agent

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 1 1958  
 CONSERVATION DIVISION  
 WICHITA, KANSAS