

15-007-00589-00-00

R CP3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Barber

Location: 2190' fr W. 1650 fr S. Sec. 32 Twp. 34 Rge. 10 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 5267

I have this date completed supervision of plugging of:

Lease Name: Helem Porterfield Well No. E 1

Operator's Full Name: Continental Oil Co.

Complete Address: Box 161, Great Bend, Kans.

Plugging Contractor: \_\_\_\_\_

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1:45AM Day 22 Month September Year 1958

The above well was plugged as follows:

267' of 8 5/8" surface casing circulated with 200 sack cement. Hole was  
filled to 250' with heavy drilling mud. 1/4 sack hulls, cementing plug  
placed at 250'. 20 sack cement placed through drill pipe. Heavy mud to  
40'. Cementing plug placed at 40' with 1/4 sack hulls below plug. 10  
sack cement placed from 40' to base of cellar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: \_\_\_\_\_  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 32 T. 34 R. 10 W  
BOOK PAGE 131 LINE 24

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 1 1958  
CONSERVATION DIVISION  
WICHITA, KANSAS

10-01-1958