

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 119-20,301-00-00 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Mesa Operating Ltd Partnership OPERATOR'S LICENSE NO. 04824

ADDRESS P.O. Box 2009, Amarillo, Texas 79189 PHONE # (806) 378-1000

LEASE (FARM) BENDER WELL NO. 1-22 WELL LOCATION 660' FSL/FWL COUNTY Meade

SEC. 22 TWP. 33S RGE. 29W (E) or  (W) TOTAL DEPTH 6150' PLUG BACK TD 6109'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 1489' CEMENTED WITH 800 SACKS

CASING SIZE 5 1/2" SET AT 6143' CEMENTED WITH 450 SACKS

PERFORATED AT 3096'-3104' (Council Grove) 5742'-5758' (Morrow) 5817'-6092' (Chester)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING CIBP @ 5720' & 3075' capped with 2 sx cement. Pull 1800'

5 1/2" casing. Spot 50 sx cement (1540'-1390'); 30 sx cement (650'-560'); 10 sx cement

(30'-0') Plugs spotted with 5 1/2" casing; mud between plugs

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 25, 1990 8:30 AM

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Sheffield, Mesa Operating Limited Partnership PHONE # (806) 378-1000

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PLUGGING CONTRACTOR Sargent's Casing Pullers LICENSE NO. 6547

ADDRESS P.O. Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.**

SIGNED: *Mark A. Town*  
(Operator or Agent)

DATE: 3/9/90

12 1990  
3-12-90  
KANSAS

①

2/9

6/90