

CP-1

RECEIVED  
KANSAS CORPORATION COMMISSION

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 SOUTH MARKET - ROOM 2078  
WICHITA, KS 67202

MAY 28 2003

CONSERVATION DIVISION  
WICHITA, KS

WELL PLUGGING APPLICATION FORM

API# 15-035-21,831-00-01 (Identifier number of this well). This must be listed for wells drilled since 1967: This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.  
WELL OPERATOR Range Oil Company, Inc. KCC LICENSE # 5120

6/03

ADDRESS 125 N. Market Street, Suite 1120 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # 316-265-6231

LEASE Maddix WELL# 4 SEC. 11 T. 33 R. 5 (EAST/WEST)

- NW - SW SPOT LOCATION/QQQQ COUNTY Cowley

1980 FEET ( in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)  
660 FEET ( in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check one: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# E-26,754

CONDUCTOR CASING                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8 5/8 SET AT 178 CEMENTED WITH 85 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3150 CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3101 to 3128' / 78 sx from 225' to surface  
*Cemented with*

ELEVATION 1257/1264 T.D. 3150 PBTD                      ANHYDRITE DEPTH                       
(GL/KB) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Bail 100' plug on bottom with 10 sacks cement. Add gel spacer to 1000'. Bail 50' plug at 1000' with 5 sacks cement. Add gel spacer to 250'. Circulate cement from 250' to surface. The 4 1/2" casing is cemented in place and will not be removed.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
If not explain why? Drilled in 1978. Scout card & KCC Enhanced Recovery Order enclosed with previous application.  
**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 ET. SEG. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Alan Nation PHONE ( ) 620-221-6345

ADDRESS Strother Field, 7710 Ninth Ave. CITY/STATE Winfield, KS 67156

PLUGGING CONTRACTOR United Cementing Co. Inc. KCC LICENSE # 30437  
(company name) (contractor's)

9/03

ADDRESS 2510 West 6th, Eldorado, KS 67042 PHONE # ( ) 316-321-4680

PROPOSED DATE AND HOUR OF PLUGGING (IF KNOWN)                      A.S.A.P.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE 5-28-03 AUTHORIZED OPERATOR/AGENT John M. Washburn

✓