

RECEIVED

MAY 30 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-20959-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Chesapeake Operating, Inc. KCC LICENSE # 32334
(owner/company name) (operator's)

ADDRESS P. O. Box 18496 CITY Oklahoma City, OK 73154-0496

STATE OK ZIP CODE 73154-0496 CONTACT PHONE # (405) 848-8000

LEASE VYN WELL# 1-13 SEC. 13 T. 34S R. 43E (East/West)

S/2 SW SPOT LOCATION/0000 COUNTY Morton

337 330 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

4646 4620 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 1400 CEMENTED WITH 550 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3277 CEMENTED WITH 155 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2940-3154' Topeka

ELEVATION KB 3361' T.D. 2575 P.B.T.D. 2558 ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ ± 2930' & cap w/20' cmt. Displace 4-1/2" csg w/9ppg abandonment mud to ±1450'. Set 100' cmt to ±1350' & displace surface csg w/9 ppg

abandonment mud & cap w/50' cmt plug
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION, AS REQUIRED? IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bud Neff PHONE# (620) 277-0803

ADDRESS 4532 W. Jones Avenue City/State Garden City, KS 67846

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # 99996
(company name) (contractor's)

ADDRESS P. O. Box 31, Russell, KS 67665 PHONE # ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 05/27/03 AUTHORIZED OPERATOR/AGENT: Randy Gasaway

Randy Gasaway (signature)

6/03

✓