

STATE OF KANSAS
STATE CONSERVATION DIVISION
CONSERVATION DIVISION
130 S. MARKET, ROOM 2078
Wichita, Kansas 67202

RECEIVED

APR 17 2003

KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM AND FILE ONE COPY)

API # 15-015-23341 - 00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

6/03

WELL OPERATOR VESS OIL CORPORATION KCC LICENSE # 5030
(owner/company name) (operator's)
ADDRESS 8100 E. 22nd St. North, Bldg. 300 CITY Wichita
STATE Kansas ZIP CODE 67226 CONTACT PHONE # (316) 682-1537
LEASE Green Trapshooter A WELL# 1 SEC. 11 T. 26S R. 04E (East/West)
SW SW NW SPOT LOCATION/QQQQ COUNTY Butler

2140 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

500 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET # _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 243' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 2387' CEMENTED WITH 335 SACKS
cmt cir

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2385-87, CIBP @ 2379; 2366-74, 1978-84, 1993-2000

ELEVATION 1361/1366 T.D. 2389' PBDT 2379' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run tubing to 2000'. Spot 75 sx Class A, 3% cc plug, pull out wireline tag.
Run tubing to 300'. Circulate hole full to surface: using 60/40 Pozmix, 6% gel,
pull out, top off. Cut off 5-1/2 csg. Cover up

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Casey Coats PHONE (316) 682-1537 X 104

ADDRESS 8100 E. 22nd Street N., Bldg. 300 CITY/STATE Wichita, KS 67226

PLUGGING CONTRACTOR United Acid & Cementing KCC LICENSE 30437

ADDRESS P.O. Box 712, El Dorado, KS 67042 PHONE # (316) 321-4680
(contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) as soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/20/2003 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

9/03

✓