

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-081-10212-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 8/03
(owner/company name) (operator's)
ADDRESS 701 S. TAYLOR, SUITE 400 CITY AMARILLO
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600
LEASE McCOY WELL# 2-32 SEC. 32 T. 28 R. 34 (xxxx/West)
- C - SE - SE SPOT LOCATION/QQQQ COUNTY HASKELL

685 660 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

779 660 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

695-KCC
Check One: OIL WELL X GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1846 CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 5491 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERF: 4686-4710, 5430-5466. PKR @ 5380.

ELEVATION 2997 / 3005 T.D. 5503 PSTD 5502 ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE X

PROPOSED METHOD OF PLUGGING BAKER MODEL D PKR @ 5380. ETOF @ 3093 (2-1/16" TBG & RODS).
DUMP 35 SXS CMT. DISPLACE WITH 9 PPG MUD TO TOP OF FISH. SHOOT OFF 5-1/2" CSG @ +/-
1870. SPOT 50 SXS FROM 1870 TO 1720. SPOT 25 SXS FROM 690 TO 615. SPOT 10 SXS FROM 40
TO 4. CUT OFF AND CAP 8-5/8" CSG 4 BELOW GL. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAWN NEASE PHONE# (620) 544-4344

ADDRESS PO BOX 40 City/State HUGOTON, KS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151

(company name) (contractor's)
ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/27/2003 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (signature)
DIVISION PRODUCTION ENGINEER

RECEIVED
JUN 02 2003
KCC WICHITA

