

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 1508110213-00-06 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 8/03  
(owner/company name) (operator's)  
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO  
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600  
LEASE McCOY FRANK WELL# 3-32 SEC. 32 T. 28S R. 34 (xxxx/West)

- - - SE SPOT LOCATION/QQQQ COUNTY HASKELL  
1980 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)  
1980 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 1860 CEMENTED WITH 750 SACKS  
PRODUCTION CASING SIZE 5-1/2" SET AT 4750 CEMENTED WITH 375 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 4689-4702

ELEVATION 3003 / NA T.D. 5531 PBSD 4711 ANHYDRITE DEPTH             
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING DUMP 40 SXS CMT AND 2 SXS HULLS TO PLUG FROM 4711 TO 4590.  
SHOOT OFF 5-1/2" CSG AT +/- 1900. SPOT 50 SXS CMT FROM 1900 TO 1750. SPOT 25 SXS CMT  
FROM 690 TO 615. SPOT 10 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8-5/8" CSG 4 BELOW GL.  
RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAWN NEASE PHONE# (620) 544-4344

ADDRESS PO BOX 40 City/State HUGOTON, KS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151 1/04

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/27/2003 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)  
DIVISION PRODUCTION ENGINEER

RECEIVED  
JUN 02 2003  
KCC WICHITA