

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1993

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-~~009~~-20034-00.00 ⁰³³ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549 ^{8/94}
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Wilmore "A" WELL# 1 SEC. 19 T. 31S R. 17 (EAST/West)

- - NW - SW SPOT LOCATION/QQQQ COUNTY Comanche

1980 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

965 FEET (in exact footage) FROM (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1017' CEMENTED WITH 600 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5155' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perf: 5034-36, 5014-24, 4878-88 CIBP: 5006'

ELEVATION 2072' T.D. 5157' PBD 5006' ANHYDRITE DEPTH NA
(G.L. ~~NA~~) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU. TIH w/1 1/4" tbg to 4900. Ld hole w/9 ppg mud. Spot 10 sxs cmt plug from 4900-4780'. TOH w/tbg. Pull 4 1/2 csg, shoot off free point. Spot 25 sxs cmt plug @ cut off point. Spot 35 sxs cmt plug from 1067-967'. Spot 10 sxs cmt plug from 34-4'.

Cut off 8 5/8 csg 4' below ground level & cap. Restore location.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? No

If not explain why? Drillers log on file

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE# (316) 624-6253

ADDRESS 1707 W. 2nd Street City/State Liberal, Kansas 67901

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151 ^{1/94}
(company name) (contractor's)

ADDRESS Rt 1, Box 49BA, Tyrone, Oklahoma 73951 PHONE # (409) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/30/93 AUTHORIZED OPERATOR/AGENT: David W. Kapple
(signature)

David W. Kapple, Division Production Engineer

ANADARKO PETROLEUM CORPORATION

PHONE 316-624-6253 • 2330 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905-0351



December 1, 1993

Kansas Corporation Commission
Conservation Division
200 Colorado Derby Building
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Well Plugging Application
UHL "A" NO. 1
1980' FNL & 1830' FWL
Section 11-31S-18W
Comanche County, Kansas

WILMORE "A" NO. 1
1980' FSL & 965' FWL
Section 19-31S-17W
Comanche County, Kansas

Dear Ms. Zadoka:

Enclosed for KCC approval is Form CP-1 (Well Plugging Application Form) on the above referenced wells.

Should you have any questions or require additional information, please contact Michael Bose at (316) 624-6253.

Very truly yours,

David W. Kapple
Division Production Engineer
BJW/cs

Enclosures

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
Ellen Cobb - HGO
WI Owners
Sargent & Horton Plugging, Inc.

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1993

CONSERVATION DIVISION
Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

December 2, 1993

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Wilmore "A" #1
API 15-033-20,034
1980 FSL 965 FWL
Sec. 19-31S-17W
Comanche County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760