

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-<sup>033</sup>~~032~~-20,653-<sup>00-00</sup> (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 155 N. Market, Suite 1000, Wichita, KS 67202 PHONE # (316) 269-7600

LEASE (FARM) Moberley "A" WELL NO. 1 WELL LOCATION 660' FNL 4620' FSL COUNTY Comanche

SEC. 29 TWP. 31S RGE. 17 (EX) (W) TOTAL DEPTH 5100' PLUG BACK TD 4960'

Check One:

OIL WELL \_\_\_\_\_ GAS WELL XX D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 516' CEMENTED WITH 375 SACKS

CASING SIZE 4 1/2" SET AT 5099' CEMENTED WITH 150' SACKS

PERFORATED AT 4983'-87', 4967'-76'

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand back to 4830'. Dump bail 2 sxs cmt.

Cut csg @ ± 3200' and POOH. Plug top w/ 2 sxs hulls, 2 gel, 125 sxs Econolite cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B, RR #1, Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Great Bend Csg. Pullers, Inc. LICENSE NO. 4835E

ADDRESS P.O. Box 768, Great Bend, KS 67530 PHONE # (316) 793-9710

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jerry Collins  
(Operator or Agent)

DATE: 10-29-87

RECEIVED  
STATE CORPORATION COMMISSION

NOV 3 1987

CONSERVATION DIVISION  
KANSAS

1

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

FEB 03 '88

EXPIRES

November 3, 1987  
WELL PLUGGING NOTICE

Moberley "A" #1  
4620' FSL 4010' FEL  
Sec. 29-31S-17W  
Comanche County

TXO Production Corporation  
155 N. Market, Ste. 1000  
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760