

15-007-20247-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

NOV 18 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Will P. Asb

Complete Address 507 Rutland St Wichita, KS

Lease Name Smith Well No. 1

Location SE/SE/NW Sec. 25 Twp. 30 Rge. 13 (E) (W) W

County Barber Total Depth 4420

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 5:00 PM Day 15 Month 11 Year 1975

The above well was plugged as follows:

196 ft 13 3/8 surface cemented with 225 sacks. 4419 ft 4 1/2 long  
string cemented with 125 sacks. Top perf. 4353 ft. Sand to 4340 ft,  
4 sacks cement with bailer. Pulled 3500 ft 4 1/2. Set 10 ft rock  
bridge at 140 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 11/18/75

INV. NO. 2269-W

HERSHBERGER ENTERPRISES, INC. #1 SMITH  
 230 O. W. GARVEY BLDG., WICHITA, KS.  
 CONTR H-30, INC. CTY BARBER

25-30-13W  
 SE SE NW

GEOL BOB GENSCHE FIELD NURSE NW

E 1876 KB c11/5/73 CARD ISSUED 4/4/74 IP P 45 BOPD + 28 BWPD  
 MASSY ZN 4353-68

API 15-007-20,247

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
COTT		2584	- 708
TARK LS		3024	-1148
TARK SD		3041	-1165
HEEB		3767	-1891
DOUG		3797	-1921
BR LS		3924	-2048
LANS		3937	-2061
MASSEY		4351	-2475
MLSS		4376	-2500
TD		4420	-2544

13-3/8" 196/225SX, 4 1/2" 4419/125SX  
 DST (1) (TARKIO) 2930-3050/30-30-30-  
 30, REC 1740' GCMW, BHP 1518-1387#  
 FP 316-922#  
 DST (2) (LANS) 4231-42/30-30-30-30,  
 REC 90'MW/TR OIL, BHP 1466-1432#,  
 FP 46-82#  
 DST (3) (MASSEY) 4345-70/30-30-60-30,  
 GTS/5", GA 51,600/5", 34,600/15",  
 21,900/30", 2ND OPEN 23,700/10",  
 28,000/20", 24,500/30", 21,900/60",  
 150' GSY OIL, 120' MO, 180' VHO &  
 GCM, BHP 1318-1077#, FP 105-187#  
 DST (4) (MISS) 4373-90/30-30-60-30, REC  
 70'M, ALL PRESS 46#  
 PF /4353-57, /4364-68, FU 800' OIL +  
 450'W, SWB DWN, 1000MA, REC LD & FU  
 (OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

REGISTRATION DIVISION  
STATE OF MASSACHUSETTS

NOV 3 1975

REGISTRATION DIVISION  
STATE OF MASSACHUSETTS

NOV 3 1975