

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AGT 19 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed September 27, 1967.CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: P. O. Box 308, Great Bend, Kansas 67530

Lease Name Neilson "A" Well No. # 1

Location C NE SW Sec. 18 Twp. 31 Rge. 17 (E) (W) W

County Comanche Total Depth 5465'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 11:30 PM Day 17th Month October Year 1967

The Above well was plugged as follows:

510' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in
the hole was at 370', 1st cementing plug, bridged with 2 sacks of dry cement and
1/2 sack of hulls on fluid at 370', and cemented with 23 sacks, through the drill
pipe, with cement from 360' to 285'. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with 2 sacks of dry cement and 1/2 sack of hulls on
fluid at 40', and cemented with 8 sacks, with cement from 30' to the base of
the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving

Well Plugging Supervisor

DATE 10/19/67INV. NO. 6524-W