

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3  
RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1981

API Number 15-033-204

CONSERVATION DIVISION  
DATE: 08-08-81

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Santa Fe Energy Co.  
 Complete Address One Security Park 7200 1-4 West Amarillo Texas 79106  
 Lease Name Vernon Well No. 1  
 Location C-5W Sec. 17 Twp 31S Rge 20W (East)(West)  
 County Comanche Total Depth 5370'  
 Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A ✓  
 Other well as hereinafter indicated       
 Plugging Contractor Da Mack Drilling Co. Rig #1  
 Address Box 1164 Great Bend Kans 67503 License No.       
 Operation Completed: Hour: 4:15 PM Day: 7 Month: November Year: 19 81  
 Plugging Operations attended by Agent?: All      Part ✓ None     

The above well was plugged as follows:

There is 639' of 8 5/8" surface casing cement circulated, 1st plug at 725' with 40 sbx of cement to cover the stone corral, which was from 695' to 703'. 2nd plug pushed rubber plug to 1000' and pumped 35 sbx of cement on top of it. 3rd plug 40' to 0' on solid bridge with 10 sbx cement. Then pumped 5 sbx cement in rat hole & 5 sbx in mouse hole.  
Plugging accomplished by Halliburton Co. out of Pratt Kans.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Paul Luthi  
Conservation Division Agent

DATE 12-21-81

INV. NO. 8791-W