

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 119-20,301-00-00

LEASE NAME BENDER

WELL NUMBER # 1-22

660 Ft. from S Section Line

660 Ft. from ^WX Section Line

SEC. 22 TWP. 33S RGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed 5/20/78

Plugging Commenced 3/28/90

Plugging Completed 3/29/90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MESA OPERATING LTD PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 04824

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Verbal on 3/9/90 to _____ (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation CG/Morrow/Chester Depth to Top 3096' Bottom 6092' T.D. 6150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Council Grove	gas	3096'	3104'	8 5/8"	1489'	None
Morrow	gas	5742'	5758'			
Chester	gas	5817'	6092'	5 1/2"	6148'	2206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set 5 1/2" CIBP @ 5720' & dumped 2 sx cement on top; RIH & set 5 1/2" CIBP @ 3075' w/2 sx cmt on top; filled hole w/9 ppg mud; shot 5 1/2" csg @ 2206' and POH; set 50 sx cmt plug from 1540'-1390' and 30 sx cmt plug from 650' to 550'; set 10 sx cmt plug from 30' to surface - welded on plate, well P&A on 3/29/90; witnessed by Glen Barlow w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pullers License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mesa Operating Ltd Partnership

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. McKee

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn L. McKee

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 30th day of March, 1990

CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:



DWAINA PITTS
 Notary Public, State of Texas
 My Commission Expires 8-6-93

RECEIVED
 STATE CORP
 4-2-90
 APR 0 1990