

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-169-19073-00 00

API NUMBER April 4, 1961

LEASE NAME Swigert SWD

WELL NUMBER 1

-- Ft. from S Section Line

-- Ft. from E Section Line

SEC. 6 TWP. 15S RGE. 2 ~~XXXX~~(W)

COUNTY Saline

Date Well Completed 4-17-61

Plugging Commenced 11-13-85

Plugging Completed 11-18-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Multistates Oil Properties

ADDRESS 3000 United Founders, #139 Ciudad Bldg., Okla. City, OK 73112

PHONE#(405) 848-8551 OPERATORS LICENSE NO. 5415

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #5 2501 Market Place Suite D, Salina, KS 67401

Is ACO-1 filed? No If not, is well log attached? Sent in with GP-1

Producing Formation -- Depth to Top -- Bottom -- T.D. --

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	80	None
				8 5/8	280	None
				5 1/2	3438	1500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

See Attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sam Mays Well Service License No. 8902

Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Deborah K. Gandy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Deborah K. Gandy

(Address) 3000 United Founders Bldg., #139 Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1986

Jana Dee Smart
Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires: April 15, 1988

JAN 10 1986

CONSERVATION DIVISION

Form CP-
Revised 08-1

Tenneco Oil Exploration and Production

A Tenneco Company



Mid-Continent Division

Ciudad Building, Suite 139
3000 United Founders Blvd.
Oklahoma City, Oklahoma 73112
(405) 848-8551

Plugging Procedures on Swigart SWD #1

11-13-85

TOOH with Tbg. and Pkr. (Tbg. in good condition).

11-14-85

TIH w/2 7/8 workstring and cement retainer. Set retainer @ 3165. RU Hall & set btm plug w/75 sx common cement witnessed by KCC rep. RU wiretech and cut casing @ 2500'. Attempt to pull csg. @ 1500'. RD W.T. TOOH w/ 5 1/2" casing.

11-15-85

Finish pulling casing. Total 48 joints.

11-18-85

RU Hall and set top plug as follows: Pump 6 sx gel followed by 50 sx common cement, 8 5/8 rubber plug, 50 sx common cement, 1/2 BW. SI @ 375 PSI. Plugging complete. Top and Bottom plug witnessed by KCC Representative.

RECEIVED
STATE CORPORATION COMMISSION

JAN 1 0 1986

CONSERVATION DIVISION
Wichita, Kansas