


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 8 Twp. 34 Rge. (E) 12 (W)

Location as "NE/CNW&SW" or footage from lines G W/2 SW NW  
Lease Owner The Atlantic Refining Company  
Lease Name V. L. Cook Gas Unit Well No. 1  
Office Address 830 Kennedy Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-6 1956  
Application for plugging filed 6-6 1956  
Application for plugging approved 6-6 1956  
Plugging commenced 6-6 1956  
Plugging completed 6-6 1956

Reason for abandonment of well or producing formation Re-entered old abandoned hole to re-test, found dry (originally drilled by Huber et al., 1947)

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5461 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				(Casing previously set)		
				10-3/4" set @ 478'		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged as follows:

5461- 470' heavy mud  
470- 400' 35 sx cement (@ 470', HOWCO plug tied off w/wireline)  
400- 60' heavy mud  
60- 30' 15 sx cement (@ 60' HOWCO plug tied off w/wireline)  
30'-surface mud  
Wooden plug in top collar.  
Completed 10:50 p.m., 6-6-56.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Corbett Drilling Company  
Address P. O. Box 4206, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.  
J. E. Hellinghausen (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Hellinghausen  
J. E. Hellinghausen, Regional Drilling Manager  
830 Kennedy Building, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 56

My commission expires 4-6-59

Wanda Davis Notary Public.  
**RECEIVED**  
STATE CORPORATION COMMISSION



**PLUGGING**  
FILE SEC 8 T 34 R 12W  
BOOK PAGE 69 LINE 29

JUN 22 1956  
6-22-56  
CONSERVATION DIVISION  
Wichita, Kansas

THE ATLANTIC REFINING COMPANY  
890 KENNEDY BUILDING  
TULSA, OKLAHOMA

WELL LOG - V. L. COOK GAS UNIT NO. 1

Location: Center of the West Half of the SW NW of Section 8-34-12W,  
Barber County, Kansas. Driftwood Field.

Lease No. KS-15,389

Elevations: Unknown

Spudded: 1-15-47 (Huber et al)

Contractor: Corbett Drilling Company, P. O. Box 4206, Tulsa, Oklahoma

Casing Record: 10-3/4" surface casing was previously set at 478' with  
1800 sacks of cement when originally completed in 1947.

COMPLETION

Well was previously plugged by Huber in 1947, and was re-entered by Atlantic  
to test the Mississippian.

5-29-56: Moved in and rigged up rotary rig.

5-29 thru 6-3: Cleaned out to total depth, 5461'.

6-4: Schlumberger ran Gamma Ray, Laterolog, Microlaterolog and Caliper surveys.

6-5: DST #1: 5460-90, tool open 2 hrs., poor blow increasing to fair. Recovered  
3900 feet of salt water, no show. IFP Off. FFP 1815#. BHPC 1995#, 30 min.

6-6: Plugged and abandoned.

\*\*\*\*\*


I, the undersigned, being first duly sworn upon oath, state that this well  
record is true, correct, and complete according to the records of this  
office and to the best of my knowledge and belief.

*J. E. Hellinghausen*  
J. E. Hellinghausen  
Regional Drilling Manager.

Subscribed and sworn to before me this 20th day of June, 1956.

*Arndt Davis*  
Notary Public

My commission expires 4-6-59



PLUGGING  
FILE SEC 8 T34 R12W  
BOOK PAGE 69 LINE 29

6-22-56  
INDEXED  
FILED