

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,855

LEASE NAME Andrews

WELL NUMBER 1

SPOT LOCATION C NE SW

SEC. 11 TWP. 34S RGE. 12 (E1/4X1/4)

COUNTY Barber

Date Well Completed 7/18/84

Plugging Commenced 7/18/84

Plugging Completed 7/18/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Dunne-Gardner Petroleum, Inc.

ADDRESS Suite 250, 200 W. Douglas  
Wichita, KS 67202

PHONE # (316) 265-1611 OPERATORS LICENSE NO. 5426

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1 Don Ubel

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5,225'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	300'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud to 500', 35 sx cement, Mud to 330', 50 sx cement,  
mud to 40', solid bridge, 10 sx circulated to surface,  
15 sx in rathole, circulated through drill pipe, 60/40  
posmix, 3%cc, 2%gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Oilwell Cementing License No. \_\_\_\_\_

Address Box 169, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Donald E. Hunt (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts stated, and matters herein contained and  
the log of the above-described well, and that the same are true and  
correct, so help me God.

(Signature) Donald E. Hunt

(Address) Suite 250, 200 W. Douglas  
Wichita, KS 67202

Subscribed and sworn to before me this 25th day of July, 19 84

Kathleen L. Greger  
Notary Public



RECEIVED  
JUL 26 1984  
7-24-84  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
SUBSCRIPTIONS  
Wichita, Kansas

My Commission expires: January 20, 1985