


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plot

Barber County. Sec. 21 Twp. 34S Rge. 10W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Texaco Inc.  
Lease Name O. R. Garner Well No. 1  
Office Address 614 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-20-1959  
Application for plugging filed 8-24-1959  
Application for plugging approved 8-28-1959  
Plugging commenced Via Verbal Authority 8-22-1959  
Plugging completed 8-22-1959  
Reason for abandonment of well or producing formation Well Drilled Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal Authority

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp  
Producing formation Dry Hole Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5830 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	272"	None
				5-1/2"	4749	4459

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED AS FOLLOWS:

Heavy Mud 4590-270  
Rock Bridge 270-260  
25 Sx. Cement 260-185  
Mud 185-35  
10 Sx. Cement 35-Surface  
Welded Plate on Surface:

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
09-15-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Smith & Smith  
Address Blackwall, Oklahoma

STATE OF Kansas COUNTY OF Sedgwick, ss.  
M. C. Harrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell  
614 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1959  
H. Howard Kistler  
Notary Public.

My commission expires September 20, 1960

PLUGGING  
FILE SEC 21 T. 34 R. 10W  
BOOK PAGE 62 LINE 34

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 11 1959  
CONSERVATION DIVISION  
Wichita, Kansas



GEOLOGICAL DATA AND DRILLING AND COMPLETION PROCEDURE

FORMATION OR DATE	TOP-DEPTH INTERVAL	REMARKS OR DESCRIPTION AND RESULTS OF WORK
		<u>REMARKS</u>
4-15-49		Spud @ 7:30 PM., H. D. Thompson operator.
4-29-59		DST #1 4696-4717 Gas to surface 30 min, 90' GCM IDH 185, IF 30, FF 55, BHP 1335/20
5-8-59		Texaco Inc. assumed operation 04:00 P.M.
5-10-59		Set 5-1/2" 14# J-55 New Casing 04760 W/75 Sxs. Pognix.
5-11-59		Ran Temperature Survey to 4737. Top Cement 04480.
5-14-59		MICF
5-16-59		Ran Grey log 4730, Cementon Log. Top Cement 4475. Perf. 4692-4714 W/4 Jets/Ft. Swabbed to 4600'.
5-17-59		Acid Perf. 4692-4714 W/300 Gal. Mud acid HP700# Min. 400# W/25# PD 5 min. zero PH Frac. Perf. 4692-4714 W/20 X 15 7-1/2 Jelled Acid wtr. HP 1400# Min. 800# W/700# PD 5 Min. On Vac. 15 Min. Tot load 538 BS
5-18-59		Ran tubing. Swabbed 190 BSW 10 Hours.
5-19-59		Swabbed and Tested perms. thru tubing. Swabbed trace oil, 348BSW 40BSW 24 Hrs
5-20-59		<u>COMPLETE.</u> Dry. Swabbed 150 BSW 12 Hrs. well abandoned. TD5830 PBTD 4737
		<u>TOPS</u>
		Stalnaker 3909 Kansas City 4190 Mississippi 4700 Viola 5070 Simpson 5152 Arbuckle 5320

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 SEP 11 1959  
 09-11-1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC. 21 T 34 R 10W  
 BOOK PAGE 62 LINE 34