

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 18 Twp. 34 Rge. 12W (W)

Location as "NE/CNW/SW" or footage from lines SE NW NW

Lease Owner Santa-Fe Pipe & Supply, Inc., (Humble Oil & Refining)

Lease Name V. L. Cook Well No. 1

Office Address Box 562, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) gas

Date well completed January 13 19 57

Application for plugging filed October 5 19 67

Application for plugging approved October 5 19 67


Plugging commenced November 7 19 67

Plugging completed November 13 19 67

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Mr. Herman Justus

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	272'	none
				5-1/2"	4899'	3452.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 4900' - 4861' - plug
- 4861' - 4800' - sand
- 4800' - 4760' - 5 sacks cement
- 4760' - 250' - mud
- 250' - 240' - rock bridge
- 240' - 165' - 25 sacks cement
- 165' - 40' - mud
- 40' - 30' - rock bridge
- 30' - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1967
12-5-67
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,

Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

T. L. Nutt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

P. O. Box 562, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 67

My commission expires July 31, 1970

Mary M. Guenier Notary Public.

COOK #1

SE/4 NW/4 NW/4 of Section 18-34S-12W Barber County, Kansas

Rigged up Rotary Tools 12/22/56

Ran 9 jts. (295.24' Used 8-5/8" Surface pipe set @ 272'. Cemented w/275 sacks Pozmix.

Tore down Rotary Tools 1/13/57

Ran 152 jts. (4907') New 5-1/2" casing set @ 4899'. Cemented w/300 sacks Pozmix.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Soil & redbed	0	100	
Shale, shells & redbed	100	1280	
Shale & shells	1280	1600	
Shale & lime	1600	3045	
Sandy lime	3045	3180	
Shale & lime	3180	3497	
Sandy lime	3497	3595	
Lime & shale	3595	4150	
Lime	4150	4310	
Shale & lime	4310	4748	
Lime, shale & sand	4748	4799	
Lime & shale	4799	4854	
Lime, shale, & chert	4854	4889	
Lime	4889	4900	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1967
10-5-67
CONSERVATION DIVISION
WICHITA, KANSAS

I, DON S. Packer, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

S/ Don S. Packer

Subscribed and sworn to before me this 18th day of January, 1957.

S/ June Swaney
Notary Public

My commission expires: July 29, 1957

(Barton County, Kansas)