

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22345-00-01  
Spot: SESESE Sec/Twnshp/Rge: 1-11S-19W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PEAVEY Well #: 1A  
County: ELLIS Total Vertical Depth: 3683 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3655		200 SX
SURF	8.625	171		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2014 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement, 10 sx gel and 600 # hulls.  
Perforations: 3215' - 3311'Shaw; LKC 3312' - 3529; open Arb.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/06/2014 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 1850', 1424' and 760'.  
Express Well Service ran in hole with tubing to 3150'. Quality rigged to tubing and mixed and pumped 10 sx gel followed by 75 sx cement w/300 # hulls mixed in. Pulled tubing to 1850'. Quality mixed and pumped 200 sx cement w/300 # hulls mixed in to circulate cement to pit area. Pulled tubing. Topped off 5 1/2" casing w/35 sx cement. Hole standing full. Rigged to 8 5/8" casing. Took 5 sx to fill casing.

GPS: 39.11857 -099.37058  
468' FSL 2971' FEL

Remarks: QUALITY OIL WELL CEMENTING TICKET# 7122

Plugged through: TBG

KCC WICHITA

MAR 10 2014

RECEIVED

District: 04

Signed \_\_\_\_\_

  
3/17/14 (TECHNICIAN)

CM

MAR 06 2014