

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20556-00-00
Spot: SESEWNWE Sec/Twnshp/Rge: 32-12S-21W
4092 feet from S Section Line, 1452 feet from E Section Line
Lease Name: RIDGWAY Well #: 2
County: TREGO Total Vertical Depth: 3918 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3916		125 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2014 10:00 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: GARY WAGNER Company: STEWART WELL SERVICE INC Phone: (785) 625-6374

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1630' w/400 sx cement
Perforations: 3916' - 3918'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2014 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3842' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 3175' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1940' and pumped 200 sx cement. Good circulation of cement. Pulled tubing out. Topped off with 20 sx cement. Hole standing full. Tied on to back side and squeezed with 15 sx cement. Shut in pressure 300 psi.

GPS: 38.96896 -099.67396

Perfs:

Top	Bot	Thru	Comments
3916	3918		.

KCC WICHITA

FEB 28 2014

RECEIVED

Remarks: ALLIED CEMENT TICKET # 54986

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

CM