

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03268-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 29-26S-20E
1287 feet from S Section Line, 1620 feet from E Section Line
Lease Name: CAMPBELL Well #: OW-12-1
County: ALLEN Total Vertical Depth: 831 feet

Operator License No.: 4485
Op Name: VERDE OIL COMPANY
Address: 1020 NE LOOP 410 STE 555
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	8	20		10 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/02/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JEFFREY L. DALE Company: _____ Phone: (620) 754-3800

Proposed Plugging Method: Drill out to original TD. Spot 20 sack plug at TD (110'). Spot 20 sack plug at 500' (110'). Plug from 225' to surface. All cement will be Class A.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 10/02/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe to TD. Spotted 20 sacks of cement through the 1" pipe at TD. Pulled 1" pipe to 500'. Spotted 20 sacks of cement through the 1" pipe at 500'. Pulled 1" pipe to 225'. Circulated cement through the 1" pipe from 225' to surface. Pulled the rest of the 1" pipe. Topped the well off with cement. A total of 225 sacks of portland cement was reported used to plug this well.

RECEIVED

FEB 13 2014

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)
8/12/14

KCC WICHITA Form CP-2/3

FEB 18 2014

RECEIVED