


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 17 Twp. 34 Rge. 10 (W) W (W)
Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 NE/4
Lease Owner Transit Corporation - Julian Oil & Royalty Co.
Lease Name Page Well No. 1
Office Address 1516 Liberty Bank Bldg., Okla. City, Oklahoma.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-24 19 55
Application for plugging filed 6-24 19 55
Application for plugging approved 6-24 19 55
Plugging commenced 6-24 19 55
Plugging completed 6-24 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas.
Producing formation Depth to top Bottom Total Depth of Well 5361 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 215 ft. with heavy drilling mud, set plug and cemented with 20 sacks cement. Filled hole to 40 ft. with heavy drilling mud, set plug and cemented to bottom of cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1955

CONSERVATION DIVISION
Wichita, Kansas

06-29-1955

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. W. Dodson (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson

Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1955

Jane A. Brady
Notary Public.

My commission expires Jan. 28, 1959.

PLUGGING
FILE SEC-127-372-10W
BOOK PAGE 127 LINE 2

15-007-00135-00-00

TRANSIT CORPORATION
Oklahoma City, Oklahoma
Driller's Log
Page No. 1

NE NE NE Sec. 23-22-15W
Barber Co., Kans.

Elevation: 1385'
Commenced: 5-23-55
Completed: 6-19-55

Formation	From	To
Red Bed & Shells	0	40
Red Bed & Shale	40	131
Shale & Shells	131	219
Red Rock	219	445
Red Bed & Shells	445	995
Shale & Shells	995	1695
Shale & Lime	1695	1795
Lime & Shale	1795	2040
Sandy Lime	2040	2140
Lime	2140	2180
Lime & Shale	2180	2480
Shale	2480	2565
Shale & Lime	2565	2870
Shale & Shells	2870	2995
Shale & Lime	2995	3070
Shale	3070	3170
Lime & Shale	3170	3255
Shale	3255	3335
Lime & Shale	3335	3377
Shale	3377	3440
Sand & Shale	3440	3511
Shale & Lime	3511	3540
Shale	3540	3620
Shale & Lime	3620	3690
Shale	3690	3840
Shale & Lime	3840	3910
Shale	3910	4005
Shale & Limestone	4005	4075
Shale	4075	4164
Shale & Lime	4164	4235
Lime	4235	5030
Shale & Lime	5030	5054
Lime (Viola)	5054	5095
Lime	5095	5112
Lime & Chert	5112	5130
Lime	5130	5141
Sand & Lime	5141	5226
Lime	5226	5260
Lime & Shale	5260	5331
Lime (Arbuckle)	5331	5361 T.D.

8-5/8" Csg. @ 219' cem. w/ 150 sx.

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1955
CONSERVATION DIVISION
Wichita, Kansas

06-29-1955

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION
BY C. W. Dodson
C. W. Dodson

PLUGGING
SEE SEC 17 T 242 10W
PAGE 129 LINE 2

Subscribed and sworn to before me this 24th day of June, 1955

My commission expires 1-28-59.
Irene A. Lundy
Notary Public