

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20238-00-00

LEASE NAME Booth

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Lee Banks d/b/a Banks Oil Company

SEC. 18 TWP. 31S RGE. 17 ~~KK~~ or (W)

ADDRESS 200 West Douglas, Suite 550, Wichita, Ks. 67202

COUNTY Comanche

PHONE# (316) 267-0783 OPERATORS LICENSE NO. 05152

Date Well Completed 1-31-78

Character of Well good

Plugging Commenced 10-26-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-1-93

The plugging proposal was approved on Oct. 20, 1993 (date)

by Dewane Rankin (KCC District Agent's Name).

Is ACO-1 filed? no / not required when drilled if not, is well log attached? no - filed earlier

Producing Formation Mississippi Depth to Top 4943 Bottom 4947-1/2 T.D. 4970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	40'	20"	40'	none
		0	546	8-5/8"	535	none
		0	4970	4-1/2"	4969	2505

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand back to 4800, dump bail 4 sk. cement, take free point, cut pipe @2505' and lay down, pump 300# hulls, 10 sk gel, 50 sk cement, 10 sk gel, 100# hulls, 8-5/8" plug 150 sk. cement max. press. 400#, ISTP 200#, all cement 60/40 poz, 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Greensburg Well Service License No. 5114

Address Box 632, Greensburg, KS 67054

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Banks

STATE OF Kansas COUNTY OF Sedgwick, ss.

Carl Shield (Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and have reviewed that the same are true and correct, so help me God.

(Signature) Carl Shield

(Address) P. O. Box 632, Greensburg, KS 67054

SUBSCRIBED AND SWORN TO before me this 10th day of November, 1993



Darlene J. May Notary Public

My Commission Expires: Aug. 28, 1996

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1993
CONSERVATION DIVISION