

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20034-00-00

LEASE NAME Wilmore "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

4315 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 19 TWP. 31S RGE. 17 W

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

COUNTY Comanche

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 9-11-68

Character of Well Gas

Plugging Commenced 1-5-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-7-94

The plugging proposal was approved on 1-1-94 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Marmaton Depth to Top 4878 Bottom 4888 T.D. 5157

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1017	0
				4 1/2	5155	2847

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pmp 1 sk hulls & 20 sxs cmt plug from 4700-4888. Displace w/mud. Shoot off 4 1/2 csg @ 2847. Spot 50 sxs cmt plug from 1060-960. Spot 40 sxs cmt plug from 500-400. Spot 10 sxs cmt plug from 40-0. TOH & 1d 89 jts csg. Cut off csg & cap 3' below ground level. KCC witnessed.

Restore location.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams


Beverly J. Williams, Technical Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 31st day of January, 19 94

Cheryl Steers
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
FEB - 1 1994
CONSERVATION DIVISION
Wichita, Kansas