

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Comanche SEC. 30 TWP. 31S RGE. 17W E/W
Location as in quarters or footage from lines:
N/2 NW NE

Lease Owner Anadarko Production Co.
Lease Name Kennedy "C" #1 Well No. _____
Office Address Box 333, Medicine Lodge, Ks. 67104
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4/24/81
Plugging completed 5/6/81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 5150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	420	None
				8-5/8" 4 1/2"	5144'	3345'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved into location. Had 15" stretch. Plugged off bottom with 35 sacks cement to 4500'. Shot and worked pipe at 4392, 4245, 4120, 3990, 3873, 3790, 3523, 3492 and 3365. Worked pipe loose and pulled total string of 78 joints, range 3. Plugged well with 15 sacks gel, 8 sacks hulls, 10 sacks gel, plug, and 150 sacks 50/50 pos 4% gel and 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May 1981

RECEIVED
STATE CORPORATION COMMISSION



Joan Kelso
Notary Public.

MAY 12 1981

CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Kennedy "C" #1
 C-N/2-NW-NE Sec 30-31S-17W
 Comanche County Kansas

Commenced: 10-5-80

Completed: 10-18-80

OPERATOR: Anadarko Production Co.

Depth		Formation	Remarks
From	To		
0	160	Sand	Ran 10 jts of 20# 8 5/8" csg set @ 420' Cemented w/ 300 sks Common PD @ 6:30 p.m. 10-5-80
160	428	Redbed	
428	1180	Redbed-Shale	
1180	2255	Shale	
2255	2590	Shale-Lime	
2590	3825	Lime-Shale	Ran 122 jts of 10 1/2# 4 1/2" csg set @ 5144' Cemented w/ 25 sks Lite Water - 130 sks Salt Sat Posmix .5 of 1% B65 - PD @ 7:15 a.m. 10-18-80
3825	5150	Lime	
	5150 - TD		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief
 and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 24th day of October, 1980.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC
 STATE OF KANSAS COMMISSION

My Commission expires February 6, 1983.

FEB 10 1981

CONSERVATION DIVISION
 WICHITA, KANSAS

