

15-007-20281-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Barber County, Sec 2 Twp 35 Rge 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines CN/2 N/2 N/2
Lease Owner Raymond Oil Co., Inc.
Lease Name Friden #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/18/73 _____ 19____
Plugging completed 6/20/73 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	323	none
				1 1/2"	4809	4210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Checked hole to 4810' and ran sand to 4750', ran 4 sacks cement.
Shot pipe at 4361', 4204', pulled 128 joints. Bailed hole to 240'
and set 10' rock bridge, ran 4 yards redi-mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1973
6-26-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of June, 19 73

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

DRILLERS' LOG

HERSHBERGER EXPLORATIONS, INC.
 No. 1 Frieden
 C N/2 N/2 N/2 of Sec. 2-35S-12W
 Barber County, Kansas

Elev: 1405 R.B.

Commenced: 3-23-72
 Completed: 4- 1-72

Surface: 323' of 8-5/8"
 cemented w/225 sx cement,
 3-24-72.

FORMATIONDEPTH

Red Bed to Red Rock	0 - 311
Shale & Shells	311 - 1380
Shale	1380 - 1630
Lime	1630 - 2720
Lime & Shale	2720 - 2965
Lime	2965 - 4800
Chert	4800 - 4810 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 4th day of April 1972.

My Commission Expires:
 August 25, 1972

Ella Priess

Ella Priess, Notary Public



RECEIVED
 STATE CORPORATION COMMISSION

MAY 24 1973
 5-24-73
 CONSERVATION DIVISION
 Wichita, Kansas

7-12-85