

15-007-2021-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Pratt County, Sec. 2 Twp. 35S Rge. 12W (E) (W)  
Location as "NE/CNW&SW" or footage from lines C SW SW  
Lease Owner Glen N. Rupe  
Lease Name Molz Well No. 1  
Office Address 925 Olive Garvey Bldg., Wichita 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 8, 19 73  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced January 8, 19 73  
Plugging completed January 8, 19 73  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Russell Biberstein of Attica)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 5187 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	202'	10-3/4"	202'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 180 Feet,  
1/2 sax Hulls, Plug and 50 sax Cement;  
Mud to 40 Feet, 1/2 sax Hulls, Plug Bridged  
and 30 sax Cement to Base of Cellar; 2 sax  
Cement in Rat Hole. Job completed @ 10 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1973  
1-15-73  
CONSERVATION DIVISION  
Wichita, Kansas


Name of Plugging Contractor Halliburton  
Address Box 693, Pratt, Kansas 67124

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Clarence Michael of Sage Drilling Co. being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael  
500 Bitting Building, Wichita, Kansas  
(Address)

Sworn to before me this 11th day of January, 19 73.

November 26, 1974



Louise K. Whitted - Notary Public.

DRILLERS LOGMOLZ NO. 1

CASING RECORD:	OPERATOR: Glen N. Rupe	DESCRIPTION:
10-3/4" @ 202' w/225 sax Cement.	CONTRACTOR: Sage Drilling Co.	C SW SW Sec. 2-35S-12W Barber Co., Kansas
TOTAL DEPTH: 5187'	COMMENCED: December 17, 1972	ELEVATION: 1436KB
	COMPLETED: January 8, 1973	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	50	
Sand & Shale	50	150	
Shale	150	205	
Shale & Shells	205	1005	
Shale	1005	1700	
Lime & Shale	1700	2157	
Shale & Lime	2157	2750	
Lime, Sand & Shale	2750	3015	
Lime & Shale	3015	3540	
Shale & Lime	3540	3675	
Shale	3675	3830	
Lime & Shale	3830	4145	
Sandy Shale	4145	4300	
Lime & Shale	4300	4483	
Lime	4483	4555	
Lime & Shale	4555	4630	
Lime	4630	5091	
Shale & Lime	5091	5129	
Shale & Sand	5129	5187	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1973  
1-15-73  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael  
Clarence Michael

Subscribed and sworn to before me this 11th day of January, 1973.

Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1974.

