

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-20,865-0000

LEASE NAME Graves A

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 4 TWP. 35SRGE. 12 (X or W)

COUNTY Barber

Date Well Completed 2-80

Plugging Commenced 7-92

Plugging Completed 7-21-92

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? See CP-1

Producing Formation Mississippi Depth to Top 4800' Bottom 4808' T.D. 4870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil/gas	0	329'	8 5/8"	329'	---
		0	4870'	4 1/2"	4870'	3350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back with sand to 4750'. Dump 5 sx common. Rip and pull 3350' 4 1/2" casing. Pump down 8 5/8" - 300# hulls, 10 sx gel, 50 sx 60/40, 6% gel, 10 sx gel, 100# hulls, 100 sx 60/40, 6% gel. MTP - 200 psi, ISIP - 200 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 31st day of July

My Commission Expires: 1-7-95

STATE OF KANSAS  
REBECCA K. CRAWFORD  
State of Kansas  
My Appt. Exp. 1-7-95

Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 3 1992  
8-3-92  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 08-84

CONTRACTOR'S WELL LOG

MAR 9 1980

OPERATOR: Ram Petroleum Corporation  
 CONTRACTOR: Union Drilling Co., Inc.  
 LEASE NAME: #3 Graves  
 LOCATION: NW NW NW Section 4-35S-12W  
 Barber County, Kansas  
 COMMENCED: February 17, 1980  
 COMPLETED: February 29, 1980

---

0	210	Red bed
210	1000	Red bed & shale
1000	3386	Shale
3386	3587	Shale & lime
3587	4010	Shale
4010	4200	Shale & lime
4200	4404	Shale
4404	4535	Shale & lime
4535	4610	Lime & shale
4610	4870	Lime
4870		TD

---

We certify that the above foregoing is a true and correct copy of the log on the #3 Graves, NW NW NW Section 4-35S-12W, Barber County, Kansas.

Union Drilling Co., Inc.

*R. D. Messinger*  
 R. D. Messinger

STATE OF KANSAS     )  
                           ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 4th day of March, 1980.

My appointment expires:  
6-2-82

RECEIVED  
 STATE CORPORATION COMMISSION  
 6-18-92  
 JUN 18 1992

*Cynthia L. Romey*  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 Cynthia L. Romey-Notary Public