

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Barber County, Sec. 12 Twp. 34S Rge. 12W(E) (W)

Location as "NE/CNW/SW" or footage from lines. C NW/4 NE/4 SE/4

Lease Owner K & E DRILLING, INC.

Lease Name Schupbach "A" Well No. 1

Office Address 719 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11/19 19 67

Application for plugging filed 11/19 19 67

Application for plugging approved 11/19 19 67


Plugging commenced 11/19 19 67

Plugging completed 11/19 19 67

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus, Nickerson, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Laid down drill pipe and plugged hole. Filled hole with heavy mud to 250'. Set plug - 1/2 sx. hulls and 25 sx. cement. Filled hole up to 40' with heavy mud and set top plug. Solid bridge & 1/2 sx. hulls with 10 sx. cement. 2 sx. cement in rathole.

Job completed @ 3:20 A.M.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.

Address 719 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. H. L. Wilson

(employee of owner) or (~~partner or proprietor~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Wilson H. L. Wilson

719 Union Center, Wichita, Kansas

(Address)

Subscribed and sworn to before me this 27th day of November, 1967

My commission expires 9-14-70



Judie K. Eby  
Judie K. Eby Notary Public.

# DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.  
719 Union Center  
Wichita, Kansas 67202

WELL NAME: #1 SCHUPBACH "A"  
LOCATION: C NW/4 NE/4 SE/4  
Section 12-34S-12W  
Barber County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: November 7, 1967  
COMPLETED: November 19, 1967  
ELEVATION: 1475' Grd; 1481' D.F.  
1484' K.B.  
PRODUCTION: Dry

CASING RECORD:  
8-5/8" @ 257' w/180 sx.

ROTARY TOTAL DEPTH: 4700'

## FORMATION RECORD

*Depths shown indicate bottom of formations encountered.*

Shale	550
Shale & Shells	1290
Shale & Lime	1890
Lime	3451
Lime & Sand	3676
Lime	4191
Shale & Lime	4260
Lime	4700

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 28 1967  
11-28-67  
CONSERVATION DIVISION  
Wichita, Kansas

## CERTIFICATION

State of KANSAS }  
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson  
H. L. Wilson

Subscribed and sworn to before me this 27th day of November, 1967.

My Commission expires: 9-14-70

Judie K. Eby  
Judie K. Eby Notary Public.

