

15-007-00051-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Barber

County. Sec. 12 Twp. 34s Rge. 12w (E) (W)

Location as "NE/CNW/SW" or footage from lines C-Se-Se

Lease Owner Woodman Iannitti Oil Co.

Lease Name Zimmerman Well No. 1

Office Address B0x 387 Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 11/18/62 19

Application for plugging approved 19

Plugging commenced 11/19/62 19

Plugging completed 11/23/62 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Justice

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set rock bridge at 200 ft. 10ft. rock- dumped 20 sacks cement - 10 ft. rock @ 40 ft. 10 sacks cement to surface. Finished : 12/00 noon Nov. 23. Plugged back to 4600 ft. dumped 5 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1962  
12-5-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Central Pipe Pulling Co.  
Address 1416 Coolidge- Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

706 Union Nat'l. Bldg, Wichita (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of Dec., 1962

My commission expires Oct. 10, 1963

Frances H. Solomon  
Notary Public.



15-007-00051-0000

DRILLERS LOG

No. 1 Zimmerman

CASING RECORD: COMPANY: Woodman-Iannitti DESCRIPTION: SE SE  
 8 5/8" @ 269' CONTRACTOR: Red Tiger Drilling Company 12-34S-12W  
 w/175 sx cement BARBER, County, Kansas  
 COMMENCED: March 25, 1961  
 5 1/2" @ 4729' COMPLETED: April 5, 1961 ELEVATION: 1460 DF  
 w/64 sx cement 1463 RB  
 TOTAL DEPTH: 4730'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil & Clay	0	40	
Red Bed Shale	40	550	
Red Bed Shale Shells	550	1390	
Shale & Shells	1390	1430	
Lime & Shale	1430	2235	
Shale & Shells	2235	2435	
Shale & Lime	2435	3165	
Lime	3165	3275	
Shale & Lime	3275	4095	
Lime	4095	4165	
Lime & Shale	4165	4250	
Lime	4250	4667	
Mississippi Lime	4667	4730	

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 5 1962  
 12-5-62  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*George A. Angle*  
 George A. Angle

Subscribed and sworn to before me this 10th day of April, 1961.

*Maurice Head*  
 Notary Public

My Commission Expires:

11-17-62