


15-007-00597-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 14 Twp. 34S Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Farney Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-23 19 58
Application for plugging filed 1-23 19 58
Application for plugging approved 1-23 19 58
Plugging commenced 7:00 P.M. 1-23 19 58
Plugging completed 10:00)PM 1-23 19 58
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Liacamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4973 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 270'. Set plug. Dumped in 1/3 sack hulls. Mixed 20 sacks cement, cement through drill pipe.

Filled hole with heavy rotary mud to 35'. Set plug. Dumped in 1/3 sacks hulls. Dumped in 10 sacks cement which filled hole to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
Jay Bowen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay Bowen
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 58

My commission expires _____
Kenneth G. Fischer, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
6-25-59

JAN 28 1958
1-28-58
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14 T 34 R 124
BOOK PAGE 79 LINE 1

DRILLERS' LOG

Farney No. 1
Loc: C SE SE
Sec: 14-34S-12W
Barber County, Kansas
Company: Honaker-Davis Drlg. Co., et al
Contractor: Honaker-Davis Drlg. Co.

Comm: 1- 7-58
Comp: 1-23-58
Rotary Total Depth: 4793'
Casing: 8-5/8" at 282'
D & A


0	30	Surface soil	
30	60	Sand	
60	270	Red Bed & Sand	8-5/8" casing cemented
270	805	Shale & Shells	at 282' with 250 sacks
805	1135	Shale & Gyp	common cement, 2% Jel and
1135	1145	Anhydrite	2% calcium chloride.
1145	1275	Shale & Shells	
1275	1735	Shale & Gyp	
1735	2000	Lime & Shale	
2000	2210	Lime	
2210	2560	Lime & Shale	
2560	2670	Shale & Shells	
2670	3225	Shale & Lime	
3225	3475	Lime & Shale	
3475	3575	Shale	
3575	3735	Shale & Lime	
3735	3810	Lime & Shale	
3810	4693	Lime	
4693	4721	Lime & Chert	
4721	4793	Lime	
4793		Total Rotary Depth	D & A

I certify that this is the true and correct copy of the above log to the best of my knowledge.



H. S. Forbes

Subscribed and sworn to before me this 27th day of January, 1958.


Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEC 14 T 34 R 12 W
BOOK PAGE 79 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1958
1-28-58