

15-087-01679-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

BARBER

County, Sec. 16 Twp. 34 Rge. 12 ~~W~~ W (W)

Location as "NE/CNW&SW" or footage from lines SW SW SW

Lease Owner PETROLEUM, INC.

Lease Name COOK "E"

Well No. 2

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed NOVEMBER 18, 1956

Application for plugging filed NOVEMBER 19, 1956

Application for plugging approved NOVEMBER 18, 1956

Plugging commenced NOVEMBER 18, 1956

Plugging completed NOVEMBER 18, 1956

Reason for abandonment of well or producing formation No Producing Zones

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives Box 8, Pratt, Kansas

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4825 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8OD	303'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 300' pushed down 1/4 sacks hulls to 300' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and place 1/4 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.

Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November 1956

John T. Brown
Notary Public.

My commission expires July 11, 1960

RECEIVED
CORPORATION COMMISSION

PLUGGING
FILE SEC 16 T. 34 R. 12W
BOOK PAGE 117 LINE 16

NOV 27 1956
11-27-56
CONSERVATION DIVISION

15-007-01679-0000
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 16 T. 34S R. 12W

FARM COOK 'E' NO. 2


LOC. SW,SW,SW

TOTAL DEPTH 4825'

COUNTY Barber Co., Kansas

COMM. November 5, 1956 COMP. November 18, 1956

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 303.25' W/225 sax.

ELEVATION 1487' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

304	Sand & red bed	Elgin	3578
1110	Red bed & shale	Heebner	3813
1135	Anhydrite	Douglas	3883
1410	Shale & shells	Lansing	4010
1430	Second anhydrite		
1605	Shale & shells		
2210	Lime & shale		
2465	Lime		
3395	Shale & lime		
3425	Lime		
3565	Lime & shale		
3765	Lime, shale & sand		
4015	Lime & shale		
4710	Lime		
4755	Mississippi lime.		
4825	Lime & shale		
4825	T. D.		

State of KANSAS }
County of BARTON } ss:

PLUGGING
FILE SEC 16 T 34 12W
BOOK PAGE 117 LINE 16

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 Cook 'E' well

RECEIVED
NOV 27 1956
11-27-56
CONSERVATION DIVISION
Wichita, Kansas

Verne A. Morris

Subscribed and sworn to before me this 23rd day of November 1956

My Commission Expires: November 12, 1958

Grandfubury
NOTARY PUBLIC