

LEASE NAME Griffin

WELL NUMBER 1-17

C SW SE Ft. from S Section Line

 Ft. from E Section Line

SEC. 17 TWP. 31S RGE. 17 (E26)(W)

COUNTY Comanche

Date Well Completed 12-10-71

Plugging Commenced 5-15-92

Plugging Completed 5-19-92

TYPE OR PRINT
 NOTICES: Fill out completely
 and return to Corps Div.
 office within 30 days.

LEASE OPERATOR Graham Michaelis

ADDRESS P.O. Box 247, Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, DLH, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filled? If not, is well log attached? yes

Producing formation Depth to Top Bottom T.D. 5101

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASINO RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	529	None
				4 1/2	5101	2400

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to - feet each set.

Sand from 5101 to 4915, 4sx with dump bailer, rip at 3230 - 3130 - 3030 - 2900 - 2800
2700 - 2600 - 2500 - 2400 - 2305 - 50sx 60-40 POZ 6% gell; 560 - 60sx - 60-40 POZ
6% gell; 60 - 20sx - 60-40 POZ, 6% gell

Steve Pfiffer and Dave Paterson on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Elmo Morgenstern


(Address) Medicine Lodge, KS

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1992

Glenda Morrison
 Notary Public
 RECEIVED 19 92
 STATE CORPORATION COMMISSION

My Commission Expires 8-17-94

MAY 22 1992



WELL LOG

COMPANY **Graham-Michaelis Corporation**

SEC. 17 T. 31S R. 17W

FARM **Griffin** NO. 1-17


LOC. C SW SE

TOTAL DEPTH **5100'**

COUNTY **Comanche, Kansas**

COMM. **11-26-71** COMP. **12-10-71**

CONTRACTOR **Garvey Drilling Company**



CASING

8 5/8" @ 529' w/400sx
4 1/2" @ 5099' w/125sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

530' Red Bed & Sand
1165' Red Bed & Shale
1238' Shale
1603' Shale & Shells
2240' Shale & Lime
2380' Lime & Shale
3965' Lime
4070' Lime & Shale
4360' Lime
5100' Lime
5100' KTD

State of **Kansas** }
 County of **Barton** } ss

I, **Charlene Marker** of **Garvey Drilling Company**
 upon oath state the above and foregoing is a true and correct copy of the log of the **Griffin No. 1-17** well.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 28 1992
 CONSERVATION DIVISION
 Wichita, Kansas

Charlene Marker

Subscribed and sworn to before me this **13th** day of **December** 19 **71**

My Commission Expires: **July 8, 1974**

George A. [Signature]
 NOTARY PUBLIC