

STATE CORPORATION COMMISSION  
130 South Market Room 2076  
Wichita, Kansas 67202

K.A.R. 82-3-117

15-033-20698-0000  
API NUMBER 15-00320698

LEASE NAME Ferrin

NOV 6 2000

CONSERVATION DIVISION  
Wichita, Kansas

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER 1-A

2310 Ft. from N/S Section Line

330 Ft. from E/W Section Line

SEC. 15 TWP. 31S RGE. 17 ~~XXXX~~ (W)

COUNTY CO

LEASE OPERATOR Oneok

ADDRESS P.O. Box 871, Tulsa, OK

PHONE# 981 588-7700 OPERATORS LICENSE NO. 4548

Date Well Completed \_\_\_\_\_

Character of Well Good

Plugging Commenced 11/1/2000

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/3/2000

The plugging proposal was approved on 11/1/2000 (date)

by Steve Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 5017 Bottom 5044 P.B.T.D. 5117

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	614	
				4 1/2	5144	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Lay down 2 3/8 tubing, displace 4 1/2 with 80 bbls. mud, set CIBP at 4970, dump 2 sx with dump bailer, fill hole with mud, cut 4 1/2 at 2200, lay down, run 2 3/8 to 1050, load hole with mud and spot 75sx, pull 2 3/8 to 640, spot 125sx, pull 2 3/8 to 40 and circulate to surface, 60/40, 6% jel

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Clarke Corporation License No. 5105

Address 107 W. Fowler, Medicine Lodge, KS 67704

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oneok

STATE OF Kansas COUNTY OF Barber, ss.

Dennis Hertel (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Dennis Hertel

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 3 day of November, 2000

Glenda Morrison  
Notary Public

My Commission Expires: 11/30/02