

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Comanche County. Sec. 15 Twp. 31S Rge. (E) 17 (W)

Location as "NE/CNWxSWx" or footage from lines C NE SE  
Lease Owner Sidwell Oil & Gas Company  
Lease Name Ferrin Well No. #1  
Office Address P.O. Box 2475 Pampa, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 27, 19 71  
Application for plugging filed October 27, 19 71  
Application for plugging approved October 27, 19 71  
Plugging commenced October 27, 19 71  
Plugging completed October 27, 19 71  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bieberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5080' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	516	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

40 sacks common cement @ 600'  
1/2 sack hulls & 10 sacks @ 40'  
2 sacks in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Leben Drilling, Inc.  
Address 100 Park Ave. Bldg. Okla. City, Okla. 73102

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of November, 19 71

My commission expires 4-29-75  
Jackie Perry Notary Public.

WELL LOG

Company Sidwell Oil & Gas Company

Sec. 15 T. 31S R. 17W

Contractor Leben Drilling, Inc.

Loc. C NE SE

Farm Ferrin #1

County Comanche


Total Depth 5080'

Casing 8 5/8"

Commenced October 10, 1971

Production

Completed October 27, 1971



Figures Indicate Bottom of Formations

0' - 103' sand  
 103' - 302' shale & sand  
 302' - 326' anhy  
 326' - 394' shale  
 394' - 981' red bed - sand - shale  
 981' - 994' anhy  
 994' - 1274' shale  
 1274' - 1945' shale & red bed  
 1945' - 2210' shale & shells  
 2210' - 2790' lime & shale  
 2790' - 3024' shale & lime  
 3024' - 3075' lime & shale  
 3075' - 3350' lime  
 3350' - 3447' shale w/lime  
 3447' - 3546' lime w/shale  
 3546' - 3897' lime & shale  
 3897' - 4197' lime  
 4197' - 4520' lime w/shale  
 4520' - 5005' lime  
 5005' - 5040' lime & chert  
 5040' - 5080' chert

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 4 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Oklahoma  
 County of Oklahoma } SS

I, Leslie Kite of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Ferrin #1 Well.

Leslie Kite

Subscribed and sworn to before me this 2nd day of Nov, 1971

My Commission Expires: 4-29-75 Jackie Perry