


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

COMANCHE County. Sec. 11 Twp. 31S Rge. (E) 17 (W)

Location as "NE/CNW&SW" or footage from lines. NW SE SW

Lease Owner STERLING DRILLING Co.

Lease Name FERRIN Well No. 1

Office Address P. O. Box 127, STERLING, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JANUARY 5 19 65

Application for plugging filed (PHONE 1-5-65) JANUARY 5 19 65

Application for plugging approved (PHONE) JANUARY 5 19 65

Plugging commenced JANUARY 5 19 65

Plugging completed JANUARY 5 19 65

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING

Producing formation Depth to top Bottom Total Depth of Well 5060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	450	8-5/8	450'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 340 FEET. SET FIRST PLUG AT 340 FEET WITH 1/2 SACK HULLS AND 25 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG AT 40 FEET WITH 1/2 SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE AND MOUSE HOLE WITH 2 SACKS CEMENT EACH.

RECEIVED
STATE CORPORATION COMMISSION

JAN 22 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. E. Hall*

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of JANUARY 1965

My commission expires FEBRUARY 1, 1968
BARBARA J. LAYTON Notary Public.

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

FERRIN #1
 NW SE SW SECTION 11-318-17W
 COMANCHE COUNTY, KANSAS

COMMENCED: DECEMBER 20, 1964
 COMPLETED: JANUARY 5, 1965

OPERATOR - STERLING DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	130	SANDY CLAY	
130	300	RED BED	
300	445	RED BED & SHALE	RAN 450' of 8-5/8" CASING CEMENTED w/350 SACKS CEMENT.
445	1075	SHALE & SHELLS	
1075	1275	SHALE & LIME	
1275	1870	SHALE & SHELLS	
1870	2040	SHALE	
2040	2635	LIME	
2635	2782	LIME & SHALE.	
2782	2890	LIME	
2890	3867	LIME & SHALE	
3867	4115	LIME	
4115	4319	LIME & SHALE	
4319	4337	BROWN LIME	
4337	4352	LACING	
4352	4425	LIME	
4425	4460	SHALE & LIME	
4460	4472	LIME	
4472	4536	KC LIME	
4536	4966	LIME	
4966	4990	LIME & SHALE	
4990	5008	LIME	
5008	5038	LIME & SHALE	
5038	5060	CHERTY LIME	
5060	TO		DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS WELL LOG FOR THE WELL DRILLED IN THE NW SE SW SECTION 11-318-17W, COMANCHE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF JANUARY, 1965, PERSONALLY APPEARED E. E. HALL, TO BE PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968

STATE CORPORATE RECORDS OFFICE
 JAN 22 1965
 NOTARY PUBLIC
 WICHITA, KANSAS