

1 040500

1-22 B-007-0011600-01 163R
API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NE, SEC. 3, T 34 S, R 12 W/E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Wright Well # 1

Operator: Graves Drilling

County Barber 154.27

Name & Address P.O. Box 8250

Well Total Depth 4747 feet

Wichita, KS 67208-250

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 22 Month: 1 Year: 19 91

Plugging proposal received from John Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4747' w/150 sx cement. Perfs at 4614-22'

1st plug sand back to 4565' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

RECEIVED
1-31-91
STATE CORPORATION COMMISSION
JAN 31 1991
CONSERVATION DIVISION

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4565' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if necessary) observe this plugging.

DATE 2-11-91

Signed Stephen J. Pfeiffer (TECHNICIAN)

INV. NO. 30666