

1 040818

1-5

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-01,024 - 00-01

SW SW SW, SEC. 3, T 34 S, R 12 W/3

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name Farney Well # 1-3

Operator: Mid-Continent Energy

County Barber

Name & Address 155 N. Market, Ste. 950

Well Total Depth 4918 159.84 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 2 p.m. Day: 5 Month: 1 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

vars: 5 1/2" at 4918' w/100 sx cement, PBSD 4888', Perfs at 4782-92'

1st plug sand back to 4730' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3 p.m. Day: 5 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 475 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-28-94

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 39834

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1994  
1-12-94  
CONSERVATION DIVISION  
Wichita, Kansas