

B

4-032107

11-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,137 *00-01*

NW SE _____ /4 SEC. 36, 14, 43 W
1730 feet from S section line
1340 feet from E section line

Operator license# 6417

Lease: Arapahoe Unit Well # 120

Operator: Union Pacific Resources

County: Wallace

Address: 15562 Highway 385
Cheyenne Wells, CO 80810

Well total depth 5300 *172.25* feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 688 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Oakley, Kansas 67748

Company to plug at: Hour: A.M. Day: 8 Month: November Year: 1995

Plugging proposal received from: Larry Bryant

Company: Union Pacific Resources Phone: _____

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs. gel. - work string.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1995
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 8, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 688' cwc with 150 sxs. 4 1/2" set at 5295' with 200sxs. P.B.T.D. 5285'. Port collar at 1987' w/150 sxs lite. Prod. perf. 5132' - 5137'. Ran work string to 5227' - displaced 50 sxs. cement blend and 300# hulls. Pulled tubing to 4589'. Displaced 25 bbls water - 13 sxs gel to 2860'. Pulled tubing to 2860' - circulated cement blend (218 sxs) to surface. Squeezed 8 5/8" with 75 sxs cement blend. Plug complete.

Remarks: GL 3903' - TOC 4256' - PC TOC 1208' - Top DK 1579' - Top Blaine 2415'.

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES _____ NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____, NO _____

Plugged through TUBING _____, CASING _____. Elevation: _____ GL

I did [] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED

DATE 12-4-1995

INV. NO. 44187

JAN 17 1996

HTD