

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,063-00-00

NW NW NE, Sec. 13, T 17 S, R 18 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Weigand Well # 1

Operator: Frontier Oil Company
Name & 1720 Kansas State Bank Bldg.
Address Wichita, KS 67202

County Rush

Well Total Depth 3715 feet 120.73

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1205

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 9 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" set at 3714 PBD at 3310 Top perfs 2782. 1st plug sand back to 2730 and dump 4 sx cement on top of sand through bailer. 2nd plug 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and dumped additional 125 sx cement.

Maximum pressure 900# and shut-in pressure 600#

Signed Steve Quont
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 9 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3714 PBD at 3310 Top perfs 2782

1st plug sand back to 2730 and dump 4 sx cement on top of sand through bailer. 2nd plug 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and dumped additional 125 sx cement.

Maximum pressure 900# and shut-in pressure 600#

Remarks: Use 60/40 Pozmix with 2% gel 3%cc by Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 2-15-84
INV. NO. 0228
2-9

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Quont
(TECHNICIAN)