

1 040390

1-4 15-007-30157-0005 49 R
API NUMBER 15- Drill Completion Date 5/6/65

REGISTRATION COMMISSION
REGISTRATION DIVISION - PLUGGING SECTION
201 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SW, SEC. 8, T 34 S, R 12 W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7382

Lease Name V.L. Cook A Well # 1

Operator: KWB Oil Property Management, Inc.
Name &
Address 15 East 5th Street, Suite 3300
Tulsa, OK 74103

County Barber 155.84

Well Total Depth 4795 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 391

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 12:30 p.m. Day: 4 Month: 1 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4794' PBTB 4775' Perfs at 4726-31, 4735-38' Junk in hole-Baker 4 1/2" AD-1 packer @ 4700'

1st plug sand 70' above packer in hole with 4 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1:30 p.m. Day: 4 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

STATE OF KANSAS
REGISTRATION DIVISION

1-8-90
JAN 8 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3600' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form)

INVOICED
DATE JAN 29 1990
INV. NO. 27216
1-4

Signed Stephen J. Pfeiffer (TECHNICIAN)