

To: 1 051532
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-21 API NUMBER 15-007-22,394 - 0000 133
NE NW SE, SEC. 11, T. 34 S, R. 12 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Operator: Allen Drilling Company
Name & Address: 7950 E. Prentice, Suite 100
Englewood, CO 80111

2310 feet from S section line
1650 feet from E section line
Lease Name Keeseeker Well # 1-11
County Barber 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address 7950 E. Prentice, Suite 100, Englewood, CO 80111

Company to plug at: Hour: 11:30 p.m. Day: 20 Month: 2 Year: 1992

Plugging proposal received from Richard

(company name) Allen Drilling Company (phone) 303-796-7350

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 600' with 50 sx cement,
- 2nd plug at 250' with 50 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 1 a.m. Day: 21 Month: 2 Year: 1992

- ACTUAL PLUGGING REPORT
- 1st plug at 600' with 50 sx cement,
 - 2nd plug at 250' with 50 sx cement,
 - 3rd plug at 40' with 10 sx cement,
 - 4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1992
2-26-92

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 3-13-92

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 34736

Expected Spud Date: January 31, 1992
 month: January day: 31 year: 1992

OPERATOR: License # 5418
 Name: Allen Drilling Company
 Address: 7950 E. Prentice, Suite 100
 City/State/Zip: Englewood, Colorado 80111
 Contact Person: Doug Hoisington
 Phone: (303) 796-7350

CONTRACTOR: License # 5418
 Name: Allen Drilling Company

Well Drilled For: Well Class: Type Equipment:
 X Oil ... Enh Rec ... Infield ... X Mud Rotary
 ... Gas ... Storage ... X Pool Ext. ... Air Rotary
 ... OHO ... Disposal ... Wildcat ... Cable
 ... Seismic: # of Holes ... Other
 If OHO: old well information as follows:
 Operator: N/A
 Well Name: N/A
 Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no
 If yes, true vertical depth:
 Bottom Hole Location:
 Exp. 7/24/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
 It is agreed that the following minimum requirements will be met:

Pusher Richard S.
 SPUD DATE 2-11-92 INIT. CS
 LENGTH SURFACE PLANNED 200
 RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
 after salt sect. _____ bbls. _____ when done _____ bbls.
 RATHOLED AHEAD? Y _____ N _____ SIZE HOLE _____
 SURFACE PIPE 8 7/8 @ 221 CONDUCTOR _____
 ANHYDRITE T- _____ B- _____ ELEVATION _____
 TD 5100 FORMATION Viola

RAN PIPE @ _____ DV TOOL _____ ALT II DONE	_____ SX _____	_____ SX _____	_____ Y _____	_____ N _____
Arbuckle Plug @ _____	_____	Ft. W/ _____	_____ SX	
Hug./Council @ _____	_____	Ft. W/ _____	_____ SX	
Anhydrite Base @ <u>600</u>	_____	Ft. W/ <u>50</u>	_____ SX	
1/2 Base Anyh. @ _____	_____	Ft. W/ _____	_____ SX	
1/2, 1/2 Plug @ _____	_____	Ft. W/ _____	_____ SX	
Bottom Surface @ <u>250</u>	_____	Ft. W/ <u>50</u>	_____ SX	
40' Plug @ <u>40</u>	_____	Ft. W/ <u>10</u>	_____ SX	

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
 WATER WELL _____ SX (Irr. Well _____ Pond _____)
 Hauling _____
 TECHNICIAN R.L. DATE 2-20-92
 TYPE OF CEMENT 60/40 #12 690gel
 STARTING TIME 11:30 (AM/PM) DATE 2-20-92
 COMPLETION TIME 1:00 (AM/PM) DATE 2-21-92
 CEMENT COMPANY Halliburton

2310' feet from South North line of Section
 1650' feet from East West line of Section
 IS SECTION X REGULAR IRREGULAR
 (NOTE: Locate well on the Section Plat on Reverse Side)
 County: Barber
 Lease Name: Keeseker Well #: 1-11
 Field Name: Grendyke
 Is this a Prorated/spaced field? yes X no
 Target formation(s): Misener
 Nearest lease or unit boundary: 1487' 330'
 Ground Surface Elevation: 1487' feet MSL
 Water well within one-quarter mile: yes X no
 Public water supply well within one mile: yes X no
 Depth to bottom of fresh water: 180'
 Depth to bottom of usable water: 180'
 Surface pipe by Alternate: X 1 2
 Length of Surface pipe planned to be set: 200'
 Length of conductor pipe required: N/A
 Projected Total Depth: 5150'
 Formation at Total Depth: Viola
 Water source for Drilling Operations:
 DNR Permit #: N/A well _____ farm pond _____ other _____
 Will cores be taken? yes X no
 If yes, proposed zone: 200' Alt. I Req.

RECEIVED
 FEB 26 1992
 2-26-92
 COUNTY OF VICTORIA, KANSAS