

1051901 2-20

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,570-00-00
C NW NE, SEC. 16, T 31 S, R 17 W/E
660 feet from NXS section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4476

Operator: Whiting Petroleum Corporation
Name & Address: 1700 Broadway, Ste. 2300
Denver, CO 80290

Lease Name Yost Well # 31-16

County Comanche

Well Total Depth 5099 165.72 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 570

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:30 a.m. Day: 20 Months: 2 Year: 19 95

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 4 1/2" at 5099' w/150 sx cement, Perfs at 5022-28'

1st plug pump 2 sx hulls and 20' sx cement on bottom,

2nd plug at 1000' with 50 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5 p.m. Day: 20 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 2 sx hulls to 4950',

Spotted through casing:

2nd plug at 1000' with 50 sx cement,

pipe stuck at 1000', shot off again at 700',

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4030' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-27-95

INV. NO. 42285

2-20

Signed Richard M. Lacey (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED FEB 27 1995