

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20698-00-00
Spot: CNWNWSW Sec/Twnshp/Rge: 15-31S-17W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: FERRIN Well Number: 1-A
County: COMANCHE Total Vertical Depth: 51450 feet

Operator License No.: 4548
Operator Name: ONEOK RESOURCES COMPANY
Address: PO BOX 871
TULSA, OK 74102 11/3

Conductor Pipe: Size feet:
Surface Casing: Size 10.75 feet: 614 WITH 500 SX CMT
Production: Size 4.5 feet: 5144 WITH 200 SX CMT
Liner: Size feet: 167.21

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/03/2000 12:45 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: DENNIS HERTEL Company: ONEOK RESOURCES Phone: (918) 588-7700

Proposed Plugging Method: SET CIBP @ 4970' & 2 SX CMT. RUN 2 3/8" TBG BACK IN HOLE TO 1050'. LOAD HOLE WITH DRILLING MUD. 1ST PLUG AT 1050' WITH 75 SX CMT. 2ND PLUG AT 640' WITH 125 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 11/03/2000 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5017-5044'. 9 7/8" HOLE TO 4000'. 7 7/8" HOLE TO 5145'. SET CIBP @ 4970' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 4 1/2" CASING. RUN 2 3/8" TUBING BACK IN HOLE TO 1050'. LOAD HOLE WITH DRILLING MUD. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 1050' WITH 75 SX CMT. 2ND PLUG AT 640' WITH 125 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 4 1/2' CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 11/9/00

INV. NO. 2001060953

NOV 07 2000

Form CI-218

MP