

1 050793

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,696-00-00
C NW SW, SEC. 15, T 31 S, R 17 W EXX
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8362
Operator: Held By Production, Inc.
Name & Address: 6021 S. Syracuse Way # 201
Englewood, CO 80111

Lease Name Ferrin Well # 1
County Comanche 127.14
Well Total Depth 3912 Topeka feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829
Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 3:00 pm Day: 10 Month: April Year: 19 86

Plugging proposal received from Wayne Bougner
(company name) Aldebaran (phone) 316-685-5372
Elevation 2095 est.

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 3912'

- 1st plug at 950' with 2 sx hulls and 50 sx cement
 - 2nd plug at 640' with 50 sx cement solid bridge
 - 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
 - 5th plug to circulate rat hole with 15 sx cement
 - 6th plug to circulate mouse hole with 10 sx cement
- Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 pm Day: 10 Month: April Year: 19 86

ACTUAL PLUGGING REPORT Lost circulation at 3870'. Squeezed hole at 3800' with 1100 sx cement, Still losing circulation. Spotted 50 sx common with 5% cc at 950'. Waited 2 hours and tagged plug at 720'. Spotted 50 sx common cement 5% cc and 3 sx hulls at 700'. Waited 2 hours and tagged plug at 655'. Spotted 50 sx 60/40 Pozmix 6% gel and 3 sx hulls at 630'. Waited 2 hours and tagged plug at 385'. Spotted cement from 40' to surface.

Remarks: Cemented by Halliburton. (If additional description is necessary, use BACK of this form.)
STATE CORPORATION COMMISSION APR 15 1986

INVOICED
APR 15 1986
I did not observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

DATE _____
INV. NO. 13455