

3-7-89

To: 051137  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,745 -00-00  
NE NW, SEC. 9, T 31 S, R 17 W X  
4620 feet from S section line  
3580 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8362  
Operator: Held By Production, Inc.  
Name:  
Address P.O. Box 1600  
Houston, TX 77251

Lease Name Kasper Well # 1  
County Comanche 166.66  
Well Total Depth 5128 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1215

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122  
Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 7 Month: 3 Year: 19 89

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Company (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1032'

1st plug at 1230' with 50 sx cement, 2nd plug at 400' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 a.m. Day: 7 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1230' with 50 sx cement,

2nd plug at 400' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 09 1989

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 3-20-89

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 24153

3-7